From:	Lorraine DeAsis
To:	Lorraine DeAsis; Jackie Pata; Ken Southerland; John Parks; Tribal Administrator (tribal.admin@craigtribe.org); Assistant Tribal Administrator
Subject:	Craig 4-plex - AMENDMENT #2 - Answers to questions
Date:	Monday, September 28, 2020 1:39:30 PM
Attachments:	Rev 2 Signed Mech.pdf

Plans – yes, these are the correct plans. We have a duplex and this 4-plex that are using the same plans.

The venting can be under the floor joists and out the kitchen, as indicated on the plans or under the floor and out through the arctic entry (wood storage).

The water heater will remain in the laundry area (rather than being moved to the arctic entry).
The water heater for the upper floor units can be vented vertically (through the roof), or as indicated on the plans and in the above sentence.

The location of the exterior heat pump unit has been corrected to the exterior of the arctic entry (wood storage).

The size of the propane tank to be set is corrected to be 100 gallon.

The propane tanks can be set under the stairs (one for each unit).

Floor joist cut sheets with hole clearances will be provided upon award of contract.

Lorraine DeAsis
Director of Project Development
(907) 780-3188
ldeasis@thrha.org

TH
Regional Housing Authority